



Life Science Products

The LYNX mission is to provide Animal Care Washing Systems of the highest standards, quality, and reliability in the industry. Our service and customer care will be unmatched.

LYNX Modular Wall System

The LYNX Modular Wall System is a custom-designed wall assembly that divides the clean and dirty areas of the Vivarium washroom. Constructed of 304 stainless steel, this wall forms an enclosure which conceals the equipment body, utility piping and wiring and also protects the workroom from excessive heat, noise and steam vapor that may be released from the washroom equipment.



Modular Wall Sizing:

The Modular Wall is specially designed and engineered to precisely fit the opening between the wall and piece of washing equipment to give a clean look to the installation.

Standard Features:

- Primary Panels
- Support Channel


Construction:

- All 304 Stainless Steel Panels
- 16 Gauge Material

Optional Features:

- Secondary Shearing Panels
- Insulated Construction
- Stainless Steel Access Door
- Louver Vents
- Stainless Steel Canopy Hood
- Seismic Anchoring

Washing • Disinfection • Filling • Conveying



[LYNX Modular Wall System](#)



Receiving Channels



Stainless Steel Louver Vent



Stainless Steel Access Doors

• Specifications are subject to change



LYNX Product Group
650 Lake Street
Wilson, NY 14172
716.751.3100 / 3101(fax)

For further information, please contact:
lynxpg.com
info@lynxpg.com • service@lynxpg.com
parts@lynxpg.com Rev 013015